


EL PASO COUNTY
COLORADO

COMMISSIONERS:
 STAN VANDERWERF (CHAIR)
 CAMI BREMER (VICE-CHAIR)

HOLLY WILLIAMS
 CARRIE GEITNER
 LONGINOS GONZALEZ, JR.

FINANCIAL SERVICES DEPARTMENT
 EILEEN GONZALES, CPPO, CPPB – CONTRACTS & PROCUREMENT MANAGER

IFB NO. 21-132

DUE DATE: OCTOBER 14, 2021

ADDENDUM NO. 1
For
LANDSCAPING, SITE PREPARATION AND INSTALLATION OF ASTROTURF
SHERIFF'S OFFICE TRAINING FACILITY

DATE OF ADDENDUM: OCTOBER 8, 2021

THE ATTACHED addendum shall become as fully a part of the above named IFB as if therein included and shall take full and complete precedence over anything contained to the contrary.

ACKNOWLEDGMENT: Each bidder shall indicate acknowledgment of receipt of this addendum by signing below and submitting this addendum **(this page only)** with the bid.

Each bidder shall be responsible for reading every item on the attached addendum to ascertain to what extent and in what manner it affects the work being proposed.

No attempt is made to list Addendum items in chronological order or in conformity with the Drawings to which they refer or which they affect.

X

NO CHANGE TO DUE DATE

CHANGE DUE DATE TO: 2:00 PM (MT), THURSDAY, OCTOBER 14, 2021
(WAS WEDNESDAY, OCTOBER 13, 2021)

I acknowledge receipt of this addendum which shall become a part of the submitted proposal.

COMPANY NAME	PHONE
AUTHORIZED REPRESENTATIVE	TITLE
SIGNATURE	DATE



The following is hereby made a part of this solicitation:

SCOPE OF WORK CHANGES / CLARIFICATIONS (RED):

- Removal of two (2) trees **and the stumps. Remove two (2) medium sized shrubs and roots.**
- Leveling land in preparation for laying AstroTurf **or equivalent.**
- Laying approximately a 44' x 100' AstroTurf with Sheriff's Logo painted on **and yard lines.**
- Rock **and mulch** landscaping **and add metal edging** around portion of facility after drainage issues have been fixed. Drainage repair will be completed by County. **Match existing 3/4" size Pikes Peak Granite.**
- **Move one (1) existing 12' x 16' wooden storage shed located on south end of the site approximately 30', per Attachment 1.**
- **Provide two (2) new 12' x 16' metal storage sheds with peaked roofs. Match existing shed height of approximately 9-10' tall.**
- **Sheds to be set on timbers treated to .60 pcf with CCA over a road base foundation.**
- **Provide heavy-duty commercial grade metal shelving, approx..36" deep, on three (3) sides of the new sheds.**
- **Provide wood framed plexiglass enclosure, approximate 6' wide x 12' x 8" high, between existing shed and first new shed with sloped roof for drainage, per Attachment 1.**

ATTACHMENTS:

1. Storage Shed Location and Detail Sketch.

END OF ADDENDUM NUMBER ONE.

All other terms and conditions of the original IFB shall remain unchanged and the subsequent bids received as a result of this solicitation shall be opened and evaluated in accordance with those terms and conditions.

Please sign the addendum signature page and return it with your bid. Failure to acknowledge this addendum in writing may be cause for rejection of your bid.

David Carey

David Carey, CPPB
Procurement Specialist